BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Schedule-B

Name of works: Improvements to drain and footpath at KG hally in ward no 12, Shettyhalli sub Division

Sl No	Description of Work	Unit	Qty	Rates	
				In Figures	In Words
1	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2018-19, Page No.142, Item No. 19.1) including Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 5 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete as per the direction of Engineer-in-charge of the work	Cum	2659.32	211.79	Rupees Two Hundred Eleven And Paise Seventy Nine Only
2	KSRRB M2100 -10. **Plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scafofolding and centering complete as per specifications MORTH Specification No. 2100	Cum	7.56	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
3	Providing laying palin / reinforced cement concrete for **side Drain using M20 nominal mix concrete** with OPC at 300 kgs with 20 mm and down size granite metal coarse aggregates at 0.69 cum fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., completet excluding cost of steel ae per MMORTH specification No 1500, 1700, 2200. including cost of materials, labour, HOM completet as per specificatios. wall and bottom thickness 15 cms	Cum	53.16	7070.20	Rupees Seven Thousand Seventy And Paise Twenty Only
4	Providing and constructing granite / trap / basalt **size stone masonry** in **basement** with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	7.45	5811.98	Rupees Five Thousand Eight Hundred Eleven And Paise Ninety Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57

5	KSRRB M2200-6 : Providing **TMT teel reinforcement for RCC work** including starightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification MORTH Specification No.1600 & 2200 - TMT Bars Fe 500	Ton	1.50	72316.38	Rupees Seventy Two Thousand Three Hundred Sixteen And Paise Thirty Eight Only
6	Removing and Refixing of slabs of Drains and pointing in C. M. (1:3)	Sqm	7212.14	111.30	Rupees One Hundred Eleven And Paise Thirty Only
7	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mmc/c bothways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials - Data rate approved by Chief Engineer, Dasarahalli zone	Sqm	81.00	2208.00	Rupees Two Thousand Two Hundred Eight Only
8	Providing and laying Pre Cast **Drain Cover slabs of 250mm thickness** including cost of all materials, labour, curing, transportation,loading, unloading etc.,complete as per the direction of Engineer - In- Charge. (Data Rate enclosed)	Sqm	82.50	5241.00	Rupees Five Thousand Two Hundred Forty One Only

Signature of Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahangara Palike,
Dasarahalli Division, Bengaluru-57